

Pre-Charged Condensing Unit



RDI

NEW



All the advantages of the "PCL" unit without the pre-charged line sets and quick connects. By eliminating pre-charged line sets and quick connects, we are able to provide "PC" units with a full charge of refrigerant* in all condensing unit sizes.

Advantages

- Available in sizes 1/2 hp up to 15 hp
- Full year labor warranty
- Full refrigerant charge (for line runs up to 50 ft.)
- Full year parts warranty

"PC" Condensing Unit Consists of:

- Condensing Unit (high side assembly) ETL Listed to UL Standard 1995
- All necessary controls for proper operation of condensing unit
- Time Clock (low temperature application) shipped loose

Standard Installed Components Include:

- Drier
- Sight Glass
- Pressure Control
- Weatherproof Housing
- Low Ambient Controls (outdoor)
- Crankcase Heater (outdoor)
- Base Valve
- Full Charge of Refrigerant

**Adequate for line runs up to 50 ft.
For longer line runs, more refrigerant
may be required.*

RDI Refrigeration Systems

81 West Holly Street, Parsons, TN 38363

Phone: 1-888-732-2446

Fax: 1-731-847-9012

4077 ©2007 RDI

Manitowoc
Foodservice Group